

Backyard Studio

Kinnebrew Construction Group

Joseph
9432703122
jkingpin1999@gmail.com
1204 Daylily Drive Southwest

Project	Cedar Lane Backyard Studio
Customer	Alisiana
Customer Email	alisia123@gmail.com
Project Address	322 Penn Station Way

Material Takeoff

Material	Quantity	Unit
20A tamper-resistant duplex receptacle	6	EA
20A white single-pole decorator switch	1	EA
2x4 x 12 ft Studs	4	EA
2x4 x 20 ft Plates	11	EA
2x4 x 8 ft Studs	50	EA
4x8 1/2 in Ceiling Drywall Sheets	7	SHEETS
4x8 1/2 in Drywall Sheets	18	SHEETS
4x8 7/16 OSB Roof Sheathing	8	SHEETS
5x10 Wire Mesh Sheets	5	SHEETS
6 mil Vapor Barrier	1	ROLLS
Asphalt Shingles (3 bundles per square)	9	BUNDLES
Compacted Aggregate Base (4 in depth)	2.61	CY
Latex Interior Wall Paint	10	GALLONS
R-13 Batt Insulation	10	BUNDLES
Ready Mix Concrete	3	CY

This report is a material estimate. Final design, quantities, specifications, and installation must follow approved plans and applicable code requirements.