

Internal Cost Sheet

Maple Street Backyard Workshop – Construction Proposal

Kinnebrew Construction Group

Joseph
9432703122
jkingpin1999@gmail.com
1204 Daylily Drive Southwest

Project	Maple Street Backyard Workshop
Customer	Daniel Brooks
Customer Email	dbrooks@gmail.com
Project Address	1842 Maple Street, Marietta, GA

Material Takeoff

Material	Qty	Unit	Unit Price	Total	Supplier
2x4 x 16.0 ft Plates	16	EA	\$12.00	\$192.00	Home Depot online reference (demo)
2x4 x 16.0 ft Top and Bottom Plates	5	EA	\$12.00	\$60.00	Home Depot online reference (demo)
2x4 x 16.0 ft Window Sills	1	EA	\$12.00	\$12.00	Home Depot online reference (demo)
2x4 x 8 ft Studs	43	EA	\$4.50	\$193.50	Home Depot online reference (demo)
2x4 x 8 ft Wall, King, and Jack Studs	18	EA	\$4.50	\$81.00	Home Depot online reference (demo)
4x8 1/2 in Drywall Sheets	23	SHEETS	\$16.00	\$368.00	Home Depot online reference (demo)
4x8 7/16 OSB Roof Sheathing	6	SHEETS	\$18.00	\$108.00	Home Depot online reference (demo)
5x10 Wire Mesh Sheets	12	SHEETS	\$38.00	\$456.00	Home Depot online reference (demo)
6 mil Vapor Barrier	1	ROLLS	\$139.00	\$139.00	Home Depot online reference (demo)
Asphalt Shingles (3 bundles per square)	24	BUNDLES	\$42.00	\$1,008.00	Home Depot online reference (demo)
Compacted Aggregate Base (6.0 in depth)	13.8 3	CY	\$125.00	\$1,728.75	Home Depot online reference (demo)
Footing System Form Boards (2x4 x 8.0 ft)	30	EA	\$4.50	\$135.00	Home Depot online reference (demo)
Latex Interior Wall Paint	5	GALLONS	\$42.00	\$210.00	Home Depot online reference (demo)
R13 Batt Insulation	12	BUNDLES	\$68.00	\$816.00	Home Depot online reference (demo)
Ready Mix Concrete	14	CY	\$150.00	\$2,100.00	Home Depot online reference (demo)

Bid Summary

Material Cost	\$7,607.25
ost	\$11,222.00
ad	\$1,882.93
	\$4,142.44
er Price	\$24,854.61

Project Labor Plan

Trade	Hours	Loaded Hourly Cost
Project Manager	6.0	\$65.00
Finish Carpenter	48.0	\$0.00
Laborer	16.0	\$35.00
Concrete Finisher	40.0	\$50.00
Carpenter	72.0	\$55.00
Roofer	32.0	\$48.00
Finish Carpenters	48.0	\$52.00
laborer	8.0	\$35.00

Notes

This proposal covers the estimated materials and planned labor for a detached 20 ft × 24 ft backyard workshop at 1842 Maple Street, Marietta, Georgia.

Scope includes site preparation, concrete footing/slab work, framing, roof sheathing, asphalt shingles, wall insulation, drywall, and interior paint as shown in the estimate.

Final layout, header sizing, structural connections, permits, electrical work, plumbing, HVAC, utility connections, grading beyond the immediate work area, and any plan-required engineering are excluded unless specifically added in writing.

Material pricing is based on supplier pricing available when this proposal was prepared and may change if work is not authorized promptly. Any work outside this scope requires written approval through a change order.

Thank you for the opportunity to provide this proposal.

This report is a material estimate. Final design, quantities, specifications, and installation must follow approved plans and applicable code requirements.